

Procedure Title	Hot Works Risk Management Procedure
Parent Policy	OHS Policy
Date Effective	March 2020
Review Date	March 2023
Procedure Owner	Manager, OH&S
Category	Operational
Version Number	1
Content Enquiries	bernadette.hayman@monash.edu
Scope	This Procedure applies to any hot works at Monash University sites in Australia.
Purpose	The purpose of this Procedure is to provide an overarching framework for the effective management of Occupational Health and Safety (OHS) associated with hot works and the corresponding increased risk of fire at Monash University sites.

Table of Contents

1.	Abbreviations	2
2.	Definitions	2
3.	Activities involving Hot Works	2
	3.1. Scoping.....	2
	3.2. Risk Assessment.....	2
4.	Hot Works Permit-to-work	3
5.	Responsibility for Implementation	4
6.	Records.....	4
7.	Document History.....	4

1. Abbreviations

BPD	Buildings and Property Division
OHS	Occupational Health and Safety
OH&S	Monash Occupational Health and Safety

2. Definitions

A comprehensive list of definitions is provided in the [Definitions tool](#). Definitions specific to this procedure are provided below.

Authorised Person: A person who is authorised on behalf of the Manager, OH&S, to approve and issue a certificate in relation to a specific type of prescribed activity.

Approved Person: A person who has been approved by an authorised person to supervise activities involving prescribed activities.

Contractor: Any person or business engaged by Monash University who enters into a contractual arrangement to conduct work for Monash University, but whose primary employer is not Monash University.

Contractor Management: The process of managing work that is being/has been outsourced by Monash University. In the context of this procedure 'contractor management' relates to OHS.

Hot Works: Any activity that involving the creation of high temperatures that have a high potential to generate a fire. Activities that typically involve hot works include the:

- Use of an exposed flame (e.g. oxy torch);
- Emission of sparks (e.g. grinding and cutting);
- Generation of radiant heat (e.g. use of cutting torches);
- Conduction of excessive heat (e.g. oxy torch, welding);
- Production of hot-by products, including waste and slag (welding).

Permit-to-work Certificate: Documented evidence of the issuing of a permit-to-work.

Permit Holder: A person who is authorised by both an approved person and the authorised person to supervise activities involving prescribed activities as documented in a permit-to-work certificate.

Sub-Contractor: Any person engaged by the principal contractor to assist with the contracted works. Any person subsequently engaged by these persons to assist is also deemed to be a sub-contractor.

Suitably Qualified Person: Person who can demonstrate that, through their experience, knowledge, qualifications and/or skills, they are competent to perform hot works and determine safe methods of controlling the risk of fire.

3. Activities involving Hot Works

3.1. Scoping

When scoping work to be undertaken and to the extent that it is practicable, it must be determined whether or not the activities will include hot works.

3.2. Risk Assessment

All hazards associated with proposed hot works must be identified and assessed prior to that work commencing. Risks that may arise include:

- Ignition of material, leading to fire or explosion;

- Fire from heat transferring to adjacent combustible materials;
- Toxic fumes generated from heated materials;
- Hazardous light intensity (e.g. lasers);

Operational managers must ensure that any risks arising from hot works activities are identified, so far as reasonable, before work commences. If there is an element of doubt, Operational Managers must consult with the Authorised Person.

Any Operational Manager directing work involving hot works must be approved to do so using the [OHS Prescribed Activities Approval Form](#).

Risk assessments must be conducted in consultation with the party who will perform the works in accordance with the [OHS Risk Management Procedure](#). The risk assessment must be documented and should include consideration and adequate control of risks. A template risk assessment is available in SARAH.

4. Hot Works Permit-to-work

Any work conducted under the management control of Monash University that may involve hot works must have a permit-to-work before commencement unless that work involves:

- Heat isolated to works and unable to spread to combustible materials, or,
- Works performed within a workplace that has been designed to accommodate hot works (e.g. within workshop or similar).

Permits are requested through Buildings and Property Division.

Permit-to-work requests must be assigned to an Approved Person in accordance with the requirements of the [OHS Prescribed Activities and Permit-to-work Procedure](#). The Approved Person is responsible for ensuring that:

- The party conducting the work has demonstrated suitable competency to perform work of this nature;
- Hazards associated with the work appear to have been identified and risks assessed;
- The intended work methods appear to be safe and without risk to health; and
- A Permit-to-work is in place before any works commence.

4.1. Conditions on a permit to work

Permit Holders must ensure that:

1. Hot works are not undertaken on a total fire ban day;
2. A fire watch is undertaken during works and for a duration of at least 1-hour post works based on the likelihood and severity of a fire occurring;
3. Flammable materials are removed or controlled to prevent ignition;
4. The appropriate number and type of portable extinguishers and other fire prevention measures are provided to the fire watch team;
5. Fire detection is in place when practicable and warranted; and
6. The work area has been isolated as far as practicable.

4.2. Monitoring

The Permit Holder must ensure that all controls identified through risk management are in place.

The Approved Person must conduct monitoring to ensure that, as far as practicable, controls identified through risk management are in place.

The Authorised Person, The Manager, OH&S, or their representative, may review the conduct of any work activities relating to hot works without notice.

5. Responsibility for Implementation

It is the responsibility of the Manager, OH&S to ensure that this procedure is implemented.

6. Records

For OHS Records document retention please refer to:

[Monash University OHS Records Management Procedure](#)

Status	<i>New</i>
Approval Body	Monash University OHS Committee (MUOHSC)
Legislation Mandating Compliance	Occupational Health and Safety Act (2004), Victoria Occupational Health and Safety Regulations (2017) Victoria
Related Policies	OHS Policy
Related Documents	<p>Australian and International Standards</p> <p>OHSAS 18001:2007 Occupational Health & Safety Management Systems - requirements</p> <p>AS/NZS 4801:2001 Occupational Health & Safety Management Systems – specifications with guidance for use.</p> <p>WorkSafe Guidance documents</p> <p>Compliance Code 'Confined Spaces', WorkSafe Victoria September 2008</p> <p>Monash University OHS documents</p> <p>PTW Procedure (BPD (Services))</p> <p>Contractor Management Procedure</p> <p>Confined Space Register</p>

7. Document History

Version	<i>Date of Issue</i>	Changes made to document
1	March 2020	Hot Works Risk Management Procedure v1